



State of Ohio Environmental Protection Agency

Southeast District Office

2195 Front Street
Logan, Ohio 43138

TELE: (740) 385-8501 FAX: (740) 385-6490
www.epa.state.oh.us

Ted Strickland, Governor
Lee Fisher, Lieutenant Governor
Chris Korleski, Director

July 23, 2009

**Re: Gallia County
Family Dollar Store
Storm Water Construction Activity
Notice of Violation
0GC01283*AG**

Mr. Thomas Littleton
TTT Construction LLC
201 West Short Street
Suite 810
Lexington, KY 40507

Dear Mr. Littleton:

On July 7, 2009, I visited your site on State Route 325 at State Route 588 in Rio Grande. The purpose of the inspection was to determine the compliance status of this site with the National Pollutant Discharge Elimination System (NPDES) permit for discharges of storm water associated with construction activity. The inspection was conducted under the provisions of Ohio's water pollution control statutes, Ohio Revised Code (ORC) Chapter 6111. The following areas need to be addressed:

Permit Coverage:

1. The permit requires the Storm Water Pollution Prevention Plan to include a description of every sediment and erosion control that will be utilized on your construction site throughout the course of the project (Part III.G.2). The SWP3 must outline the proper use of the control; it should describe at what time during the project the control(s) will be implemented; and which contractor is responsible for the construction and maintenance of the control(s). **Please send a copy of the storm water pollution prevention plans to Aaron Wolfe at the Ohio EPA Southeast District Office at 2195 Front Street Logan, Ohio 43138.**
2. Part III.G.2.b.i. (Table 2) of the permit requires that any area that will lie dormant for more than 21 days, but less than a year be stabilized within 7 days of the most recent disturbance. Temporary seeding may be accomplished any time between March 1 and November 1. Any seeding that occurs between November 1 and the spring seed will be considered dormant seeding. **Stabilize all areas that do not meet this requirement.**

3. In accordance with Part III.G.2.d.i. and Part III.G.2.h. of the permit, all sediment control structures shall be functional throughout the course of earth disturbing activities. Sediment controls should be in place prior to the onset of construction activities and must remain in place until the entire up slope area is stabilized.
The storm water controls from the storm water pollution prevention plans need to be installed immediately.

Please be advised that failure to comply with the terms and conditions of your NPDES permit may be cause for enforcement action pursuant to the Ohio Revised Code Chapter 6111.

Sediment and erosion controls for your site must meet the guidelines and design criteria set forth in the above mentioned *Rainwater and Land Development* manual. A copy of this manual may be obtained by contacting the Ohio Department of Natural Resources, Division of Soil and Water Conservation, at (614) 265-6610.

Within fourteen (14) days of receipt of this letter, please submit to me at this office a written notification as to actions taken or proposed to eliminate violations of the permit. Your response should include the dates, either actual or proposed, for the completion of the actions. If you have any questions, please contact Aaron Wolfe at (740) 380-5277 or me at (740) 380-5413.

Sincerely,



Dustin Tschudy
Storm Water Section
Division of Surface Water

DT/dh