



**Environmental  
Protection Agency**

Governor  
Lt. Governor  
Director

August 1, 2011

RE: LAKE COUNTY  
PERRY TOWNSHIP  
PERRY TOWNSHIP PARK  
CONSTRUCTION STORM WATER

Walter Siegel  
Perry Township  
3740 Center Road  
Perry, OH 44081

Dear Mr. Siegel:

On July 26, 2011, I performed an inspection at the above-referenced site to determine compliance with the Ohio EPA General Storm Water National Pollutant Discharge Elimination System (NPDES) Permit for Construction Activities #3GC04950\*AG. Our records indicate that Perry Township was granted coverage under the NPDES permit on June 8, 2010.

It appears that construction activities are complete and the site has been stabilized. Please be aware that NPDES permit coverage must be terminated within 45 days of when the site reaches final stabilization. Final stabilization means that all soil disturbing activities at the site are complete and a uniform perennial vegetative cover (i.e., evenly distributed, without large bare areas) has reached a growth density of 70% or greater on all unpaved areas and areas not covered by permanent structures. Equivalent stabilization measures such as the use of landscape mulches, rip-rap or gabions may be employed, where appropriate, in lieu of vegetation. In addition, all temporary erosion and sediment control practices must be removed and disposed and all sediment trapped by these practices must be permanently stabilized.


In addition, post-construction water quality best management practices (post-construction BMPs) must be installed and a long-term maintenance plan must be provided to the party that will be responsible for long-term maintenance of those practices, e.g., homeowners' association. Post-construction BMPs are permanent site features that will remain in perpetuity to improve the quality of storm water runoff from the development site. Examples of post-construction BMPs include, but are not limited to, extended detention basins, bioretention cells (or "rain gardens"), sand filters, permeable pavement and enhanced swales. In some cases post-construction BMPs include non-structural preservation areas such as riparian setbacks and conservation easements.

Please review your site to determine if it has reached final stabilization and ensure that post-construction BMPs have been installed. *Please consult with Frank Walland, MS4 Program Manager to make this determination.* If you determine that your site has reached final stabilization, you must submit a Notice of Termination (NOT) to Ohio EPA to terminate NPDES permit coverage. The form and instructions are available on our website at [www.epa.ohio.gov/dsw/storm/stormform.aspx](http://www.epa.ohio.gov/dsw/storm/stormform.aspx). If you determine that your site does not yet qualify for an NOT, please provide me with a letter of explanation indicating why NPDES permit coverage cannot yet be terminated. Please submit the NOT or letter of explanation no later than August 15, 2011.

WALTER SIEGEL  
AUGUST 1, 2011  
PAGE 2

If you have any questions, please contact me at (330) 963-1128.

Sincerely,

A handwritten signature in black ink, appearing to read "Tim McParland". The signature is written in a cursive style with a large, prominent initial "T" and "M".

Tim McParland  
Assistant to the District Engineer  
Division of Surface Water

TM:bo

pc: Frank Walland, Perry Township, MS4 Program Manager  
Board of Trustees, Perry Township  
Lake SWCD