



**Environmental
Protection Agency**

Ted Strickland, Governor
Lee Fisher, Lt. Governor
Chris Korfeski, Director

Re: Lucas County
Fallen Timbers Community Church
Construction
Storm Water

December 1, 2010

Reverend Jeff Wheeland
Fallen Timbers Community Church
1200 Michigan Avenue
Suite B
Waterville, Ohio 43566

Dear Reverend Wheeland:

On November 4, 2010, I inspected Fallen Timbers Community Church located at 7215 Noward Road, Waterville Township. The purpose of the visit was to evaluate compliance of the site with the National Pollutant Discharge Elimination System (NPDES) permit for storm water discharges associated with construction activity (Construction General Permit), Facility ID No. 2GC01756. The inspection was conducted under the provisions of Ohio's water pollution control statutes, Ohio Revised Code (ORC) Chapter 6111. Ohio EPA has no record of other permittees for this project.

At the time of my visit, construction activities appeared to be complete. A building had been constructed and the parking areas and drive were paved. Please be aware that a Notice of Termination (NOT) must be filed to relieve you of the obligation to comply with this general permit, including the obligation of routine inspections. A NOT may be filed if one or more of the following conditions have been met:

- Final stabilization has been achieved on all portions of the site for which the permittee is responsible. Final stabilization means that all soil disturbing activities at the site are complete and a uniform perennial vegetative cover of at least 70% density has been established over the entire site. All temporary erosion and sediment control measures have been removed, properly disposed of, and all trapped sediment is permanently stabilized.
- Another operator(s) has assumed control over all areas of the site that have not been fully stabilized.


Your site does not yet appear to meet all of the conditions mentioned above. There remained a few areas where the grass cover had not yet reached a 70% density, such as south of the drive. Also, it was not immediately evident if post construction storm water management facilities had been installed that meet permit requirements. Under the conditions of the permit, Fallen Timbers Community Church is required to install one or more of the permanent structural post-construction Best Management Practices (BMPs) listed in Table 2 of the permit to treat the water quality volume (WQv) and ensure compliance with Ohio's Water Quality Standards listed in Ohio Administrative Code 3745-1. An additional volume equal to 20% of the WQv is to be incorporated into the BMP for sediment storage and/or reduced infiltration capacity. Drain times must meet those in Table 2 of the permit.

Please submit information demonstrating how the post construction storm water management requirement is being met within 10 days of the date on this letter. Your reply should include a statement about the type(s) of BMPs implemented, a site map showing the location of each practice, a delineation of its tributary drainage area and its size, and the basis for its design. For each control include: the calculations of the Water Quality Volume (WQv), a detail drawing of the structure with relevant elevations, stage-storage tables, and release rate calculations. Runoff coefficients must be based on those contained in Table 1 the permit. If a weighted runoff coefficient is being used, include supporting calculations. Your reply must address how the Post-Construction requirement will be met for all disturbed areas.

When a uniform perennial vegetative cover has reached a growth density of 70% across the entire site and the post construction storm water management requirements have been met, you will be eligible to submit an NOT application form. The NOT form and instructions can be found on our website:
<http://www.epa.ohio.gov/dsw/storm/stormform.aspx>. NOTs must be filed with Ohio EPA's Central Office within 45 days of when the above criteria are met.

If there are any questions, please contact me at (419) 373-3009.

Sincerely,



Lynette Hablitzel, P.E.
Division of Surface Water
Storm Water Program

/llr

pc: (DSW-NWDO File)

Brian Miller, P.E., Assistant Drainage Engineer, Lucas County Engineer
Jeff Grabarkiewicz, Lucas SWCD, Lucas County SWCD
Eric Gay, Zoning Inspector, Waterville Township
Waterville Township Trustees, c/o Kay Ann Robertson, Fiscal Officer



State of Ohio Environmental Protection Agency

Northwest District Office
347 North Dunbridge Road
Bowling Green, OH 43402-9398

Return if not called for in 10 days



Resent 12/8/10
7215 Noward Rd
Waterville 43566

UTF

Lynette H

neopost[®]
12/01/2010
US POSTAGE

FIRST-CLASS MAIL

\$00.44⁰




ZIP 43402
041L11212724

REVEREND JEFF WHEELAND
FALLEN TIMBERS COMMUNITY CHURCH
1200 MICHIGAN AVENUE
SUITE
WATERVILLE

NIXIE 430 5E 1 00 12/03/10

RETURN TO SENDER
NOT DELIVERABLE AS ADDRESSED
UNABLE TO FORWARD

BC: 43402939847 *2046-19467-01-35



43402@9398
43566+1050