



2GC0224720100805

WOOD BRENTWOOD PARK DETENTION POND 2GC02247 2010/08/05 CLEMENT, SARAH NORTHWOOD



**Environmental
Protection Agency**

Ted Strickland, Governor
Lee Fisher, Lt. Governor
Chris Korfeski, Director

Re: Wood County
Brentwood Park Detention Pond
Construction
Storm Water

August 5, 2010

Ms. Patricia Bacon
City of Northwood
6000 Wales Road
Northwood, Ohio 43619

Dear Ms. Bacon:

On July 12, 2010, Judson Delancey and I inspected Brentwood Park Detention Pond at 2100 Tracy Road in Northwood, Ohio (pictures taken). The purpose of our visit was to evaluate compliance of the site with the National Pollutant Discharge Elimination System (NPDES) permit for storm water discharges associated with construction activity, Facility ID No 2 GC02247*AG. The inspection was conducted under the provisions of Ohio's water pollution control statutes, Ohio Revised Code (ORC) Chapter 6111. As a result of this inspection, your site may be eligible for termination of your NPDES permit.

It appears that construction activities at Brentwood Park Detention Pond are near completion. The detention pond had been constructed and stone aprons had been placed at the outfalls. Accordingly, a Notice of Termination must be filed to relieve you of the obligation to comply with this general permit. An NOT may be filed if one or more of the following condition are met:

- Final stabilization has been achieved on all portions of the site for which the permittee is responsible. Final stabilization means that either:
 1. All soil disturbing activities at the site are complete and a uniform perennial vegetative cover of at least 70% density has been established over the entire site. All temporary erosion and sediment controls measures have been removed, properly disposed of, and all trapped sediment has been permanently stabilized; or
 2. For construction projects on land used for agricultural purposes, final stabilization may be accomplished by returning the disturbed land to its pre-construction agricultural use. If not returned to its pre-construction agricultural use, the land must meet the final stabilization criteria of (1) above.

Ms. Patricia Bacon
August 5, 2010
Page 2

- Another operator(s) assumes control of all areas of the site that have not been fully stabilized.

Your site does not meet all the above criteria at this time. The bottom of the detention pond did not have a vegetative density of at least 70%. I recommend that this area be reseeded in order to achieve the appropriate uniform vegetative cover.

When a uniform growth density of at least 70% has been achieved over the entire site, you will be eligible to file a Notice of Termination (NOT) form. The form can be found on our website: <http://www.epa.ohio.gov/dsw/storm/stormform.aspx>. NOTs should be filed within 45 days of when the above criteria are met.

If there are any questions, please contact me at (419) 373-3025.

Sincerely,



Sarah Clement
Division of Surface Water
Storm Water Program

/llr

pc: DSW-NWDO File: