



40 years *moving forward*

John Kasich, Governor

Mary Taylor, Lt. Governor

Scott J. Nally, Director

July 1, 2013

Bill Heifner
Riener Construction
2164 City Gate Drive
Columbus, OH 43219

Re: Notice of Violation at Chesrown Cheverolet, Buick & GMC / Delaware County. Permit #: 4GCO00099*AG

Dear Mr. Heifner:

This letter is written regarding a storm water inspection I conducted with Jerome Hoke and Rachel Bellis of the Ohio EPA at Chesrown Cheverolet, Buick, GMC located on Hull Drive in the city of Delaware on June 19, 2013. The Agency understands these construction activities are currently covered under the General Storm Water Permit Associated with Construction Activities. Based on the site inspection and the General Storm Water Permit, the following items must be addressed:

Sediment and Erosion Controls:

- Two primary sediment basins have not been installed per the approved plan, resulting in direct violation of the Olentangy General Permit. According to the approved storm water pollution prevention plan, sediment basins are required prior to initial grading activities.
- During the inspection, we spoke with the superintendent, who agreed to install the basins within 7 days. Please ensure positive flow to the basins intended for sediment control for all affected areas during active construction.
- Be aware the General Permit states that all barren areas which remain idle in excess of 21 days must be protected from erosion within seven days of the last earth disturbing activities. In addition, erosion protection must be implemented for all areas of final grade within seven (7) days.

- **Erosion Control Requirements:** Please be aware the General Permit mandates specific permanent and temporary stabilization requirements. All disturbed areas which remain idle in excess of 21 days must be protected from erosion within seven days of the last earth disturbing activities. All areas of final grade must be protected within seven days. All earth disturbing activities should be clearly logged in your inspection reports to ensure the 21 day / seven day requirement is not violated.
- **Maintenance Requirements:** The General Permit requires the permittee to conduct inspections of all sediment and erosion controls every seven days or within 24 hours of a rain event equal to or greater than 0.5 inches. A log of the inspections and resulting corrective actions must be maintained on site available for review. All earth disturbing activities must be clearly documented in your inspection reports to ensure the temporary or permanent stabilization requirements are not violated.
- **Post Construction Requirements:** The General Storm Water Permit requires specific post construction water quality treatment for all sites. Guidance regarding the post construction mandates can be found at: <http://www.epa.state.oh.us/dsw/storm/CGPPCQA.aspx>. Please submit to my attention (email preferred at harry.kallipolitis@epa.state.oh.us) which practice will be installed at this site to ensure compliance with the General Permit. Please include all design criteria with your submittal.

If you have any questions regarding this letter or the inspection, please do not hesitate to contact me at our Central District Office at (614) 728-3844. Follow-up inspections will be conducted to ensure the conditions of the General Permit are continuing to be met.

Sincerely,



Harry Kallipolitis
Storm Water Coordinator
Division of Surface Water
Central District Office